

**SYMBOLS**

- ↑ Arrow board
- ▮ Trailer mounted sign
- ⌋ Sign
- ⊕ Type II barricade, drum, or vertical barricade with monodirectional flashing light

- ① The Road Construction Ahead sign shall be located 3 to 5 miles in advance of the project limits.
- ② The message board shall be used to display status of lanes within the project. The primary messages shall be:  
"Right Lane Closed" / " x Miles Ahead"  
"Left Lane Closed" / " x Miles Ahead"  
"All Lanes Open"
- ③ Three, Type II barricades, drums, or vertical barricades at 25' (8 m) centers.
- ④ This sign shall be used when 2 lanes are closed.
- ⑤ This sign shall be omitted when median width is less than 10' (3 m).
- ⑥ This sign shall only be used if the existing speed limit is greater than 65 mph.


**GENERAL NOTES**

This standard is used where at any time a lane is closed on a freeway/expressway. When the left lane is closed, LEFT LANE CLOSED signs shall be substituted for the RIGHT LANE CLOSED signs.


The first sign and the message board are stationary.


The last four signs and arrow board shall be moved as necessary to maintain the required distance from the start of the lane closure taper(s).

All dimensions are in inches (millimeters) unless otherwise shown.



Illinois Department of Transportation

APPROVED January 1, 2024  
  
ENGINEER OF SAFETY PROGRAM AND ENGINEERING

APPROVED January 1, 2024  
  
ENGINEER OF DESIGN AND ENVIRONMENT

ISSUED 1-1-04

| DATE   | REVISIONS  |
|--------|--|
| 1-1-24 | Moved flashing light from the side to top center of lane closed signs. |
| 1-1-22 | Corrected work zone speed limit sign number.                           |

APPROACH TO  
LANE CLOSURE,  
FREEWAY/EXPRESSWAY

STANDARD 701400-12